CHERENKOV DETECTOR FOR SANE

Brad Sawatzky Temple University


21 April 2005

Overview of Talk


- \rightarrow Comment on Backgrounds.
- \rightarrow Overview of Draft Design.
- \rightarrow Future Plans.

REFERENCE DESIGN

- Goals
 - High electron detection efficiency
 - Pion rejection factor of at least 1000:1
- Some details
 - Operation at roughly atmospheric pressure
 - Radiator: dry nitrogen at 20°C, n=1.000279
 - Pion momentum threshold: 5.9 GeV
 - Electron momentum threshold: 21.6 MeV







BACKGROUND RATES IN 5" PMT

- Detector at 40° and 12 m from target
- 59 μ A on 4 cm LD₂ target

Threshold	Rate
$50 \text{ mV} (\approx 1 \text{ p.e. thr})$	310 kHz
100 mV	154 kHz
150 mV	84 kHz

- (saw similar rates for $59 \,\mu\text{A}$ on 1% C target)
- Pb shielding in place:
 - \rightarrow 2" Pb in cylinder around PMT
 - \rightarrow 8" Pb (total) between target and PMT
- Worst case: $BG \propto r^2$
 - $\rightarrow r \approx 1.2 \,\mathrm{m} \Rightarrow \mathrm{solid} \ \mathrm{angle} \ \uparrow 100 \times$
 - $\rightarrow \mu A$ on pol. target $\downarrow 100 \times$
 - \rightarrow How does BG production off NH₃ compare to 4 cm LD₂ (?)

FUTURE WORK...

- In-Hall parasitic tests weren't satisfactory
 - \rightarrow "best" result: 4–5 p.e.'s with CO₂

 $(\Rightarrow \lambda_{\text{cutoff}} \approx 400 \,\text{nm...})$

- → poor resolution of Hamamatsu PMT could also lead us to underestimate #p.e.'s using $N_{\text{pe}} = \left(\frac{\mu - \text{ped.}}{\sigma}\right)^2 \dots$
- \rightarrow Benchtop tests using ⁹⁰Sr β emitter with quartz radiator
 - In this controlled environment we will study:
 - \rightarrow better determination of actual # p.e.'s
 - \rightarrow actual mirror reflectivity
 - (incl. sample from Glass Mountain Optics)
 - \rightarrow actual PMT performance

UPCOMING TIME-TABLE...

- Mirrors
 - \rightarrow Vendor: Mountain Glass Optics (4–6 week delivery)
 - \rightarrow Sample ordered for evaluation.
- PMTs
 - \rightarrow Vendor: Photonis (XP4318/B) (4-6 week delivery)
 - \rightarrow Have sample to test.
- Frame Design
 - → Essentially complete.
 (PMT mounts to be finalized.)
- Frame Construction
 - \rightarrow Vendor: (already lined up)
 - (8 weeks after final drawings delivered)

Bottom line: Expect to have all components in hand by late summer 2005.