

# Pre-Adult CEBAF

## The remaining two years of adolescence


Arne Freyberger  
Accelerator Operations  
Accelerator Division

**Jefferson Lab**

November 8th, 2010

# 6GeV CEBAF: Milestones


- 1987-02-01** Construction Begins
- 1993-12-23** Construction Ends
- 1994-07-01** First Beam on Target, one-pass beam to Hall-C
- 1994-09-01** Freyberger starts work at CEBAF
- 1995-02-01** First Polarized Beam
- 1995-11-01** CEBAF reaches design energy of 4GeV
- 1999-08-01** Highly polarized beam with Strained GaAs
- 2005-01-01** Really really highly polarized beam with super-lattice photocathode
- 2008-09-15** CD3 approval for 12GeV project, construction begins super-lattice cathode



Both are results of successful SBIR Programs

# 12GeV Upgrade

Gun/source upgrade not part of the 12GeV upgrade (except for new slits required since Hall-D is a low current hall).



- Increase the 5-pass beam energy to 11GeV
  - Install 10 C100 cryomodules, ~doubles RF gradient
  - Upgrade magnets to handle increase in beam energy
- Add a tenth Arc and new extraction line at end of North Linac
- Add fourth transport line and hall (Hall-D)
- Maximum beam power remains at 1MW for 12GeV machine. Maximum beam current at 11GeV

# 6-month down: The pre-upgrade

May 2011 → Nov. 2011

## 12GeV activities

- LCW upgrade, no LCW until Sept. 15th
- CHL preparation for CHL-2, no 2K cryogens for the first month
- PSS upgrade, no PSS system until mid-August
- Arc Dipole Magnet modifications, require access to the North and South linac for magnet transportation
- 2 C100 installed and commissioned.
- Beam for physics in November 2011. Users expect same beam quality as if none of this work occurred.

## Implications on Positron Experiment

- Need to provide temporary supplemental LCW
- Need to provide for PSS system in the Injector
- Beam restoration starts October: Any invasive positron modifications must be backed out by Oct. 1. This is much longer than the nominal restoration period due to the amount of check-out that is required.

But non-invasive equipment can remain in place, this will allow for additional positron measurements if the halls are unable to receive beam.

# 12-month down: The upgrade

May 2012 → May 2013

## 12GeV activities

- Magnet modifications, require access to the North and South linac for magnet transportation
- 8 C100 installed and commissioned.
- Arc10/Injector chicane reconfiguration.
- Beam Commissioning scheduled to start May 2013, physics program resumes late 2014 or 2015.

## Implications on Positron Experiment

- Source/Gun region will need to be available for  $\frac{1}{4}$  crymodule, gun and warm RF work
- Plans for this work are still very tentative at this point.

## Other activities

- C100 installed in Injector 0L03 or 0L04
- Possible other injector upgrades
  - new  $\frac{1}{4}$  crymodule install
  - 200keV upgrade
  - warm RF reconfiguration

# $e^+$ on the horizon?

- Physics potential of 4GeV CEBAF was **greatly** enhanced by:
  - the introduction of polarized beam and continual improvement in the beam polarization from 30%→85% or slightly higher.
- Beam properties in terms of Energy and Current are well constrained in the 12GeV era.
- Beam polarization presently at the high 80% will be difficult to improve and gains from any improvement will not be overly significant.

Integrating a polarized positron source with the 12GeV CEBAF will increase the physics reach of the 12GeV program. It may be the only way to go beyond the present physics scope

# END HERE!!!

Thank You for your time and attention.