

PEPPo Experimental Apparatus & Operations

Joe Grames
PEPPo Collaboration Meeting
November 8, 2010


Two topics:

- Fabricating & installing the PEPPo experimental apparatus
- Running "CEBAF" during 6-month shutdown



SLAC E166 - Experimental Apparatus:


Fortunately, the experimental apparatus is largely based upon (and borrowed from) the SLAC E166 experiment (NIMA **610** (2009) 451–487)



JLab Experimental Apparatus:

1. Polarized photons will be replaced by polarized electrons (PEPPo concept):

CEBAF Injector
 $P=85\%$, $E=2-8\text{ MeV}$, $I < 10\mu\text{A}$




2. We do not plan (need) to measure the exiting photons.

Photon target T1
Solenoid SL
Spectrometer D2
Reconversion target T2
Polyethylene shielding
Lead wall
CsI calorimeter
Analyzing magnet TP1
Positron counter P1
Collimator C3

Positron diagnostics

PEPPo Apparatus: basically 3 systems

new e- beam spigot, e⁺ collection, Compton polarimeter.



New e-beam "spigot"

Issues/Punchlist:

Decide exactly where we "break into" beam line => footprint (see later slide)


"new" mechanical layout

Parts straight-forward, but still lead time

Fabricate/purchases can begin soon, assembly too

Target ladder most "unique"

Basic design review, don't expect big "show stoppers"




Integrating E166 components:

Issues/Punchlist:

Solenoid/Dipole not on-site yet
Analyzing magnet leaving DESY any day...

Target/solenoid integration
Dipole exit port in wrong location
Dipole field map (& densimet) a concern
Revitalize jaws for momentum selection

Vacuum, mechanical, controls TBD
So, still much to do...




Integrating E166 components:



On the positive side, we benefit greatly from being able to calibrate system with precision electron beam.

With this in mind we may consider:


- A. Using the photon line port as a diagnostic
- B. Modifying region between exit port and reconversion target to improve calibration and collection




Complication or Improvement - Part 1?



Complication or Improvement - Part 2 ?



Exit window is reconversion foil




Running CEBAF during 6-month shutdown

Significant work in the accelerator for 12 GeV upgrade (mid-May to mid-November, 2011) precludes running beam into cryomodules.


Injector will have typical maintenance activities, but within usual 6-8 week span

Operation will require., "segmenting" injector and it's systems from rest of CEBAF

- Final beam termination point
- Radiation shielding
- Personnel controls



First pass PEPPo Footprint



Will consider moving line downstream (of BCM, easier shielding)


LCW Requirements: Again, the Big Hippo

Injector Positron LCW Spreadsheet



System	System Owner	Item	Location	Flow (GPM)	Heat Load
RF	EESRF	Chopper/Buncher system	IN01B07	1.0	
RF	EESRF	0L02 Klystrons	IN02B17	25.0	
RF	EESRF	MO Amplifiers	IN01B15	4.0	
RF	EESRF	Pre-Buncher	Tunnel Zone 1	2.0	
RF	EESRF	Capture	Tunnel Zone 1	10.0	
Beam Device	EESIC	A1	Tunnel Zone 1	1.0	
Beam Device	EESIC	A2	Tunnel Zone 1	1.0	
Beam Device	EESIC	A3	Tunnel Zone 2	1.0	
Beam Device	EESIC	A4	Tunnel Zone 2	1.0	
Beam Device	EESIC	Chopping apertures (5)	Tunnel Zone 1	3.0	
Beam Device	EESIC	P-Cup	Tunnel Zone 1	0.5	
Beam Device	EESIC	FC1	Tunnel Zone 1	1.0	
Beam Device	EESIC	FC2	Tunnel Zone 2	1.0	
Beam Device	EESIC	500keV/Mott dumps	Tunnel Zone 2	2.0	
Beam Device	EGG	Positron Dump	Tunnel Zone 2	2.0	
Beam Device	EESIC	5MeV Dump	Tunnel Zone 2	2.0	
Magnet	EESDC	QJ (5)	Tunnel Zone 2	3.0	
Magnet	EGG	PEPPo - target solenoid	Tunnel Zone 2	2.0	
Magnet	EGG	PEPPo - dipole spectrometer	Tunnel Zone 2	2.0	
Magnet	EGG	PEPPo - capture solenoid	Tunnel Zone 2	2.0	
Magnet	EGG	PEPPo - analyzer solenoid	Tunnel Zone 2	2.0	
			Totals (GPM)	68.5	0

PSS Gate: Maybe not too bad...


- Move gate back ~2 meters
- Maintain Egress
- Area Rad Monitor ~ Operations
- Beamline Monitor ~ Loss/Strikes




Radiation Control Group - Pass 2




Beam on Target: 8MeV & 10 μ A on 1mm thick W



Beam on Dump: 8MeV & 10 μ A on "thick" dump



Beam Strike: 8MeV & 10 μ A loss above cryolines



Resources & Schedule

Broad Labor Requirements - configure segmentation, install PEPPo, run PEPPo, re-configure segmentation

Utility Interruptions - LCW (low conductivity water) will not be available for majority of shutdown, cryogenics will not be at 2K (for SRF) early in shutdown

Activity	Start Date	Duration
Shutdown Begins	May 14	-
Segmentation/PEPPo Installation	May 16	7 weeks
Run PEPPo/Mott Programs	July 5	9 weeks
Backout Segmentation	September 5	2 weeks
Recommission Injector	September 19	2 weeks
CEBAF Recovery	October 3	6 weeks
Shutdown Ends	October Y	-

Summary

- Top priority has been assessing if/how we run CEBAF during shutdown
- The Compton polarimeter analyzing magnet should arrive in December.
- Ready to begin mechanical layout of electron beam spigot; then review/modify - want to begin fabrication/assembly by January, must identify resources to instrument/control beam line
- Next issue is to ship the E166 solenoid/spectrometer to JLAB
 - Highest priority over next ~couple months
 - Need to assess "new" diagnostic section
- RadCon making progress - next iteration requires better ME layout, particularly location

Tomorrow, we'll discuss work integration & planning in more detail, however, we need to converge on final design layout and by end of this year have detailed roadmap for 2011.