

Ecal Overview

Raphaël Dupré


IPN Orsay
CNRS-IN2P3
Université Paris-Sud

Unité mixte de recherche

**CNRS-IN2P3
Université Paris-Sud**

91406 Orsay cedex
Tél. : +33 1 69 15 73 40
Fax : +33 1 69 15 64 70
<http://ipnweb.in2p3.fr>

Outline



→ Upgrades

- Mandatory
- Optional

→ Monitoring & Calibration

→ Installation in the Hall B

→ Software

→ Main Structure for crystals, cooling and electronics

- Done
- Might need some adjustment due to electronic changes

→ Vacuum Chamber

- Done

→ ECal new mounting system

- To be finalized

→ Design work to be done in Orsay

- Construction by JLab or Orsay?

Motherboards

→ **Need to be changed**

→ **New Design**

- We have less constraints now
- To be done by INFN

→ **Construction**

- INFN or Orsay?

→ Design

- Using design from Orsay Engineer for CLAS12 Fwd Tagger build by INFN

→ Settings

- Need to be adjusted to HPS (depends a lot on APDs)
- Tests in Orsay to adjust gain, S/B and time window

→ Construction

- Construction by Orsay

→ Optional

→ Increase the area from 5x5 to 10x10mm

- Would increase the light collection significantly

→ Better S/B (Tests by Andrea)

- Improve the electron identification for the whole experiment
- Allow to measure cosmics directly

→ Issues

- Money
- Schedule

→ Track based calibration

- Main calibration channel using electrons
- Needs tracking → Cannot be used for monitoring

→ Cosmic MIPs

→ Light Monitoring using LED


→ Neutral Pion detection

- **Around the noise level in the ECal**
- **New APDs**
- **Specific trigger**
 - **Pattern recognition in the Ecal (need specific run)**
 - **Outside trigger (scintillator bars on top of Ecal)**
- **Slow process**
 - **Probably not fast enough for monitoring**

- **Injecting light in crystals to check efficiency and gains**
- **We need to design a system completely**
 - **Optic fiber injection or LED directly on the crystal?**
 - **Can we do that for end of 2014?**
- **What precision and how relevant?**
 - **These systems are known to be difficult to setup**
 - **Radiation damages might affect differently the monitoring system and the actual data**
- **Should be funded in Orsay (TBC)**


Pi0 Calibration

→ Using Pi0 peak might help calibration




Pi0 Calibration

→ Large Coverage of the Detector



→ Acceptance down to 700 MeV



- **Needs to be tested with background**
 - Can we resolve the peak directly?
 - Do we need veto from tracker?
- **Rates have to be evaluated**
 - Important to know if it qualifies for monitoring

Schedule

ECAL	230 days	Mon 9/2/13	Fri 8/1/14
Fix 2-shorted HV groups on top-left	1 wk	Mon 9/2/13	Fri 9/6/13
Order new motherboard	6 wks	Mon 9/2/13	Fri 10/11/13
New motherboards and amplifiers	8 wks	Mon 10/14/13	Fri 12/6/13
New pre-amplifier boards	6 wks	Mon 9/2/13	Fri 10/11/13
Assembling ECAL	3 mons	Mon 1/20/14	Fri 4/11/14
Test and Calibrate Ecal	4 mons	Mon 4/14/14	Fri 8/1/14
New mounting system	4 wks	Mon 1/6/14	Fri 1/31/14
ECAL Ready for the installation	0 days	Fri 8/1/14	Fri 8/1/14

→ Mostly constrained by electronics upgrades and light monitoring construction

→ Detailed schedule need to be developed for the review

→ In particular for the light monitoring and the electronics upgrades

- **Final geometry is in the Geant4 MC (SLIC & GEMC)**
 - But readout need to included
- **Readout effects need to be implemented**
 - Needed to match data with simulation
- **Reconstruction Software**
 - Existing
 - New cluster algorithms can be tested
- **Monitoring Software**
 - To be done

Summary

→ Hardware Updates

- In good progress in Orsay & INFN
- New APDs or not? When is the dead line?

→ Monitoring

- No clear solution yet, but time to make decision

→ Installation Schedule

- To be improved

→ Software

- Need man power