Accelerator Operations

Eduard Pozdeyev

Director of Accelerator Operations

Monday, February 10, 2025









Last Year's Goals and Performance

Deliver beam to three halls for nuclear physics program safely and reliably	✓	Delivered beam to ACBD with 76% reliability vs 77% promised.
Execute CEBAF Performance Plan	✓	SFR delivered two C75CM and one C100. Reliability scope had to be reduced due to funding.
Improve CEBAF reliability: reduce unscheduled downtime and frequency of trips	✓	Noticeable improvement in critical systems. See next slide.
Improve CEBAF multi-hall performance with a high beam intensity	✓	Improvements demonstrated. Need more work.
Prepare for upcoming experiments to meet users' requirements	✓	Work in progress. Work with SMEs. Support beam studies.
Enhance CEBAF capabilities through AIPs	✓	Progress with LLRF and BPM.
Maintain strong operations team capable of meeting operational challenges	≪	Operator team reaches full strength.



Reliability Comparison FY24 to FY23

- Significant improvement in RF, Beam Transport, and Magnet reliability
 - Improvement due to focus on maintenance, beam tuning, and their optimization
 - CMs added to CEBAF as part of CPP increased energy margin
 - Lower beam intensity last run and three Halls
- Incident with the Gun Laser negatively affected reliability


Category	FY23 Downtime, h (/%)	FY24 Downtime (h/%)	Progress (in relative terms)
RF	300 (7%)	222 (4%)	-37% ↓
Beam Transport	244 (6%)	156 (3%)	-45% 🔱
Magnets/DC	229 (5%)	72 (1%)	-73% ↓
Gun	2 (0%)	353 (7%)	+16717% 个
Scheduled hours	4307	5027	



Technical Improvements: Increasing Beam Power

Increased beam power from 800 to 900 kW by the end of the run


- CPP added Cryomodules
- Plasma processing in South Linac
- RF/LLRF
- 13 kW Klystrons
- Q_L adjustment






Technical Improvements: Reducing Beam Losses

Installation of 4 additional ion chambers helped to reduce losses in some locations by an order of magnitude.








Talk Title Here 5

Technical Improvements: New Injector

New injector was commissioned in FY24. Significant improvements of the gun and transport solenoids this SAM.



Technical Improvements: CPP Energy Reach Work


- Upgraded two C20 CMs to C75 CMs (2L05 and 1L09)
 - Each add approximately 40 MeV gain
- Installed refurbished 1L22 CM
 - Added approximately 30-35 MeV gain

• Injector 0L03 (C20 CM) He processing to meet injector energy requirements



Technical Improvements: Plasma Processing (PP)

- Last year results
 - Field emission free operation was improved by 59.1 MeV (24%).
 - An average improvement of 2.7 MV/m.
 - 5 cavities were field emission free after processing.
- Four NL CM and one SL CM, were PP
- This year PP showed mixed results. Some cryomodules demonstrated gains comparable to last years. However, others showed decrease in field emission on-set.
- We believe PP works but suspect contamination.
- No PP until we understand what happened.
- We will have to drive North Linac cryomodules harder to get required energy.





Technical Improvements: Other

- Near term improvements
 - Fast BPM acquisition system in the machine to better understand and mitigate energy and orbits oscillations (HyperNuclear, MOLLER)
 - Band-Aid before NextGen BPM AIP Upgrade
 - Fast feedback
 - Energy spread control for HyperNuclear
 - MOMOD
 - Synchrotron Light Interferometer for precise energy spread measurement
- Long term future Upgrades
 - Degrader for to test transport of large emittance e+ beam
 - Test of permanent magnets for 22 GeV Upgrade



Impact of Safety and Compliance Related Issues

- Delayed start of CEBAF due to safety pauses twice
- Reduced moral and loss of expertise, including critical
- Reliability improvement initiatives and work on upgrades had to be postponed until resources are available
- We expect that ePAS and High Hazard High Consequence work policy will increase response time and affect the machine reliability
 - Working with the ES&H to understand and mitigate impact
 - We are likely to incur at least 5% reduction in reliability



Budget Perspective

- Last year CPP Reliability budget was significantly reduced no obsolescence and reliability upgrades
- Funding issues and late release of procurements did not allow us to start the North Linac CM lifetime improvement initiatives.
- Slow AIP development (LLRF, BPM, Timing System, Beam Loss Monitors)
- This year CR
 - Effectively reduced by inflation
 - Late availability of money (start-stop)
- DOE communicated to plan CPP assuming no increase in budget
 - Budget increase is required for additional vacuum work and addressing reliability issues
 - Not having Degradation addressed will cause us to continue spending effort on CM refurbishment



Next Run

Next run: March 7 – Sep 2

Halls: ABCD

• Energy: 1060 MeV/linac

Beam power: 900 kW

Polarization: ABCD

Reliability goal 80%

- RF and SRF are on critical path for start of beam recovery in CEBAF
- Injector beam work is on going
- 1L09 work completed: 2/26
- Beam recovery begins: 2/21
- Physics begins: 3/7



Run Risks

- Technical requirements are challenging: higher energy, beam power, and reliability.
- Staffing in support groups
- ePAS and HHHC impact on uptime
- Technical and schedule impact of safety pause, new rules (safety, procurement, etc.), and delays still are not completely understood
- Budget
- Run continues late into the summer

