

# SANE

## Spin Asymmetries of the Nucleon Experiment (TJNAF E07-003)

### Basics of experiment



Measured polarized beam- polarized target asymmetries with target spin oriented  $0^\circ$  and  $80^\circ$  to the beam direction.

Experiment runs in both orientations at beam energies of 4.7 and 5.9 GeV . Calibration at 2.4 using  $0^\circ$  orientation.

# SANE Physics

- Measure **proton** spin structure function  $g_2(x, Q^2)$  and spin asymmetry  $A_1(x, Q^2)$  at four-momentum transfer  $2.5 \leq Q^2 \leq 6.5 \text{ GeV}^2$  and Bjorken  $x$   $0.3 \leq x \leq 0.8$ 
  - **Meets or Exceeds DOE 2011 Milestone for Proton Spin Structure**
- Goal is to learn all about proton SSF's from **inclusive double polarization measurements** of parallel and near-perpendicular spin asymmetries
  - twist-3 effects from third moments of  $g_2$  and  $g_1$ :
    - $d_2$  matrix element =  $\int_0^1 x^2 (3 g_2 + 2 g_1) dx$
  - comparisons with Lattice QCD, QCD sum rules, bag models, chiral quarks
  - Study  $x$  dependence (test nucleon models) and  $Q^2$  dependence (evolution)
  - Exploration of "high"  $x$  region:  $A_1$ 's approach to  $x = 1$
  - Test polarized local duality for final state mass  $W > 1.4 \text{ GeV}$
- Detect electrons with **novel large solid angle electron telescope BETA**



# World data on $A_{\parallel}$ , $A_{\perp}$ and SANE kinematics



SANE



- Two beam energies: **5.9 GeV**, **4.7 GeV**
  - (small loss if **5.7 GeV**)
- Very good high  $x$  coverage with detector at  $40^\circ$  (plot from BETA's GEANT simulation)

# SANE Expected Results



- $x$  dependence at constant  $Q^2$  and  $Q^2$  dependence at fixed  $x$  (illustrative binning only)
- data are concentrated in the region most sensitive to  $x^2 g_{2,1}$ 
  - (estimates based on 75% beam and target polarization, and 85 nA beam current)

# SANE Expected Results (II)



- Improve total error on  $d_2(Q^2 = 5 \text{ GeV}^2)$  by factor  $< 0.5$ ; systematics dominated
- Constrain extrapolations of  $A_1^P$  to  $x = 1$  within  $\pm 0.1$  (using duality)
- SANE's measured  $A_2$  will improve world's  $A_1$  data set


## Overview of changes in Hall C

1. Polarized target
  - a. 5T field to polarized target with direction orienting spin
  - b. When  $80^\circ$  to the beam direction need magnet chicane to direct beam upwards at angle before target field so beam parallel to vertical at target.
  - c. No vacuum connection between target chamber and beam line.
  - d. FSD triggered by loss of target field.
2. Exit beam line is a short aluminum snout attached to helium-filled bag.
  - a. When field at  $0^\circ$ , beam into regular beam dump
  - b. When field at  $80^\circ$ , beam deflected down ( 2.2 deg at 5.9 GeV and 2.8 deg at 4.7 GeV) into in-hall beam dump.
3. New girder directly upstream of target
  - a. Install SEM to measure beam position
4. Use slow raster ( 1cm radius) in addition to the fast raster. FSD on slow raster.
5. Average current will be 80-200nA ( calibration at 2.4 GeV uses 1uA)
  - a. Need BPM sensitive to these low currents
  - b. Need upper limit for current
6. Use chicane for  $80^\circ$ 
  - a. Need magnet voltages in the FSD

## Experimental Schedule


1. Oct. 25-29 E=2.4 parallel target , commissioning.
2. Oct 30-Nov 2 E=4.7 parallel target, commissioning.
3. Nov 3-9 E=4.7 parallel target, production.
4. Nov 10 rotate target to perpendicular running. Modify chicane.
5. Nov 11-16 E=4.7 , perp target, commissioning. ( Different backgrounds compared to parallel config)
6. Nov 17-Nov 30 E=4.7, perp target, production.
7. Dec 1 Change beam energy to 5.9, Modify chicane.
8. Dec 2-21 E=5.9, perp target, production
9. Jan 14-23 E=5.9 , parallel target, production. ( Target rotated and chicane modified during down time)

# Overview of the hall






# Close up view




# Chicane



- BZ dipole magnet
  - Max. current: 500 A
  - Eff. Length: ~ 2 m
  - Gap: 3.81 cm
  - Power Supply: 40V/500A


- BE dipole magnet
  - Max. current: 300 A
  - Eff. Length: ~ 1 m
  - Gap: 2.54 cm
  - Power Supply: 40V/320A

# Rear Windows of Helium Bag



# Beam Dump

Walter has drawings for dump, will be installed after the G0 magnet is removed.



| ZONE | REV.              | DESCRIPTION                  | DATE               | APPROVED                          |
|------|-------------------|------------------------------|--------------------|-----------------------------------|
| J    | INCORP. ECO #1021 | JRS JUN02                    | 08AUG02            | W OREN                            |
| K    | INCORP. ECO #1031 | JRS NOV03                    | 14JAN04            | S Suhring<br>H Arell<br>W Kellner |
| L    | INCORP. ECO #1032 | JRS JUL04                    | 08OCT04<br>12OCT04 | S Suhring<br>H Arell<br>W Kellner |
| M    | INCORP. ECO #1034 | JRS MAR05                    | 16NOV05<br>07DEC05 | W Kellner<br>H Arell<br>S Suhring |
| N    | INCORP. ECO #1035 | OK'D TW SOMARDO<br>JRS MAR06 | 07APR06<br>16APR06 | W Kellner<br>H Arell<br>S Suhring |
| P    | INCORP. ECO #1036 | JRS JUL06                    | 28AUG06<br>13SEP06 | W Kellner<br>H Arell<br>S Suhring |
| Q    | INCORP. ECO #103x | JRS SEP07                    |                    |                                   |


Polarized target  
Usual currents 0.1 uA  
For commissioning 1.0 uA

In addition to fast raster  
will have slow raster for  
2cm diameter beam

Replaced girder  
No harps  
BPM  
YG viewer  
SEM  
BCM (< 1uA)


PRELIMINARY  
17SEP07

In Hall beam  
dump





Replace beam pipe  
with helium bag with  
aluminum snout

- NOTES
1. INSTALLATION PER CEBAF DWG 28401-E-0293.
  2. 'SOS' DIPOLE IS LOCATED FOR DRAWING CLARITY NOT TRUE POSITIONING.
  3. SCATTERING CHAMBER & BEAM LINE INSTALLED PER DWG 57153-56001.



- LEGEND  
(Indicating Lowest Energy Line Shown)
- 0I - Injector
  - 0L - Pre-accelerator
  - 2R - Second Recombiner
  - 1L - First Linac
  - 1S - First Spreader
  - 1E - First Extractor
  - 1A - First Arc
  - 1R - First Recombiner
  - 2L - Second Linac
  - 2S - Second Spreader
  - 2E - Second Extractor
  - 2A - Second Arc
  - 2C - Transport Channel



| AREA  | SIGNATURE      | DATE     | DATE | DATE | DATE |
|-------|----------------|----------|------|------|------|
| VAC   | Scott Williams | 05/12/06 |      |      |      |
| INSTR | Karel Capak    | 05/14/06 |      |      |      |
| MAG   | Mark Wiseman   | 05/14/06 |      |      |      |
| OPS   | Steve Suhring  | 05/14/06 |      |      |      |
| ALIGN | Chris Curtis   | 05/06/06 |      |      |      |

|              |                        |
|--------------|------------------------|
| GWDD ID. NO. | 284050038revQ          |
| APPROVALS    | DATE                   |
| DRAWN        | JACKI R SMITH 12/09/05 |
| CHECKED      | Chris Groves 05/03/06  |
| APPROVED     | W OREN 05/16/06        |
| APPROVED     | SEE LEFT               |

|             |   |
|-------------|---|
| PROJECT     | CEBAF   |
| DESCRIPTION | BEAM TRANSPORT MACHINE CONFIGURATION LINE 'C'- HALL 'C' |
| DWG NO.     | 28405-E-0038  |
| SHEET       | 1 OF 1  |