# CLAS12 - TORUS Magnet

*The CLAS12 Toroid* is based on six superconducting coils around the beam line to produce a field primary in the azimuthal ( $\phi$ ) direction. The choice of this configuration leads to an approximate toroidal field distribution around the beam axis. The Torus design was driven by the following physics requirements:

- Large acceptance for forward going particles (50% particle acceptance in detectors at 5 degrees from beam axis)
- Good momentum resolution
- 6 fold symmetry around the beam axis
- Large bore to allow passage of scattered primary beam



# TECHNICAL PARAMETERS

#### PARAMETER

#### **DESIGN VALUE**

Toroidal Field Geometry
6
Double pancake potted in Aluminum Case
124
25,500
117
234
SSC outer dipole cable soldered in 20 mm x 2.5 mm Cu channel
0.003" E-Glass Tape <sup>1</sup> / <sub>2</sub> Lap
3770
882,000
3.58
Inner turn near warm bore adjacent to cooling tube
Yes
2.78 @ 5 degree , 0.54 @ 40 degree
2.00
14.2
Hard wired quench detector / $0.124 \Omega$ dump resistor
Conduction Cooled by Supercritical Helium
4.6
Min 1.52 (@5.3 K) to Generation temperature 6.82
LN2 Thermo-Siphon

## • Construction Strategy:

- JLab lead the design effort
- JLab procured the soldered conductor
- □ FNAL manufactured 8 coils and potted them in the coil cases (CCMs)
- JLab assembled each coil into cryostats in an on-site factory
- All 8 coils tested at 80K
- The six coil torus assembled and tested as a magnet in Hall B

### • Significant Dates:

June, 2015

- □ August 1, 2013 7 conductor spools soldered
  - December 1, 2013 Practice coil delivery to JLab
  - January 2, 2014 Prototype coil fabrication start
- Oct 17, 2014 Begin erection of the Torus assembly tooling in Hall B
- □ Nov 1, 2014 Complete coil fabrication process (Practice CCM001)
- □ Nov, 2014 First CCM delivered to JLab for Cryostating
- □ February 6, 2015 First coil delivered to Hall B
- □ May 11, 2015 4th Coil installed on Installation Spit
  - June, 2015 Last CCM delivery to JLab
    - 6th Coil installed on Torus
  - January, 2016 Magnet Assembled and off the Assembly Spit
- □ August 2016 Cooldown Starts
  - September 2016 Torus at 4 Kelvin
- □ November 2016 Torus commissioned and field mapped in Hall B

# Project Status 3/15/2017

- □ Magnet achieved full field
- □ Small internal helium leak is not effecting performance
- □ Lower vacuum pump system will have Turbo Pump moved to low field region

Last Updated: March 22, 2017







**Contact:** 

D. Kashy, Technical Lead (<u>kashy@jlab.org</u>) (757)-269-7275
V. D. Burkert, Hall B Group Leader (<u>burkert@jlab.org</u>) (757)-269-7540