


HPS Test Run Tracking and Vertexing: Status and Plans



Tim Nelson - **SLAC**

HPS Collaboration Meeting - JLab

5/26/2011



Task Assignments

- Hybrid and DAQ Design - [SLAC](#) (w/ [UCSC](#))
- DAQ Assembly - [SLAC](#)
- DAQ Testing - [SLAC](#) (w/ [UCSC](#))
- Hybrid Assembly - [UCSC](#)
- Hybrid Testing - [UCSC](#) (w/ [SLAC](#))
- Sensor Testing - [UCSC](#)
- Mechanical and Cooling Design - [SLAC](#) (w/ [FNAL](#))
- Support Fabrication - [SLAC](#) (w/ [FNAL](#))
- Module Assembly and Testing - [SLAC](#) (w/ [UCSC](#))
- Tracker Assembly and Testing - [SLAC](#) (w/ [UCSC](#))




Schedule

- Time and resources are constrained: important to understand schedule limitations
- Developed a detailed, resource-loaded schedule for delivery of the tracker
- Care has been taken not to “back in” to the schedule from any required completion date.
- In general, this schedule is consistent with other schedule exercises.
(e.g. independently developed DAQ schedule from Ryan)
- Good news: there is some float between this schedule and our official schedule, which itself includes some contingency.

http://www.slac.stanford.edu/~tknelson/HPS/Tracker_TR.html






Critical Path



Key Milestones



Produced a set of key milestones from completion of major tasks

Quite a lot has to happen this Summer to meet flurry of milestones in the Fall



Critical Path Items

🔸 Critical path: Hybrid and DAQ

Limited by effort available from Ryan and others in Haller group.

🔸 Close behind: Mechanical and Cooling systems (esp. module supports)

Limited by effort available from Marco and FNAL.

Not much can be done elsewhere to speed things up, so it is important to keep the pipeline full on these tasks and find shortcuts on them that reduce schedule risk wherever possible.



Status and Plans

Work is underway in a number of areas

 Silicon testing and qualification

 DAQ design

 Mechanical and cooling design

 *Software*



Silicon Status




❏ **CV Curves: bias voltages**
Will be able to operate most if not all of test run at 150V bias.

Sensor	Full Depletion Voltage [V]	Full Depletion Voltage + 10% [V]
1800	132.4	145.64
1801	135.5	149.05
1802	135.0	148.5
1803	132.6	145.86

❏ **IV Curves:**
 leakage currents and breakdown voltages
Quality of sensors for radiation tolerance appears excellent

❏ **Wirebonding Tests:**
 Ensure that metallization on sensors in long-term storage at FNAL still in good condition:
Sensors appear fine.



Silicon Plans

UCSC

- ❖ Reached same conclusion as DØ Run IIb effort: testing presents greater hazards to channel yield than building and selecting best modules.
- ❖ Will only perform IV curves to identify sensors meeting highest breakdown voltage specification.
- ❖ Can have silicon tested and ready within a few weeks.



Hybrids and DAQ Status

SLAC

🍯 Draft hybrid schematic is under review

🍯 <https://confluence.slac.stanford.edu/display/hpsg/Hybrid>

🍯 RTM schematic is under review and in layout queue

🍯 <https://confluence.slac.stanford.edu/display/hpsg/RTM>



Comments on both currently being collected on confluence to move designs forward as quickly as possible.





Hybrids and DAQ Plans

SLAC

Hybrids

-  After schematic approval, work on layout and mechanical design begins: requires close collaboration between Ryan and Marco.
-  Met with Geoff Hall Monday at CERN and have agreement to purchase APV25 chips as soon as payment can be arranged

RTM

-  After schematic approval and layout complete, goes to fabrication. It's a big board and layout takes time...
-  A mini-RTM (single-hybrid readout) is planned so DAQ testing and development can continue while full RTM proceeds in parallel.

Mechanical Design Status **SLAC**

- ❏ Conceptual design is as complete: full design requires concrete specs
- ❏ Cooling and Mechanical Specifications: under review and taking comments
 - ❏ https://confluence.slac.stanford.edu/display/hpsg/Mechanical+and+Cooling+Specifications+-+*DRAFT*
- ❏ Fabrication of CF-composite for module supports: **FNAL**
 - ❏ Discussing with Bill Cooper regarding fiber specifications and layup requirements for module supports.
 - ❏ Must determine if necessary material is in hand or needs to be ordered.



Mechanical Design Plans

SLAC

- ✦ With final specs, Marco will complete modeling and calculations necessary to engineer details and validate solutions.
- ✦ FNAL will acquire materials (if not in hand) and begin fabrication of required sheets of CF-composite.
- ✦ Want to have support prototype in hand by the time we have hybrids so we can proceed immediately to module assembly
- ✦ Design and fabrication of assembly fixtures is last major task: very important not to overlook this.



Summary

- ❖ Aggressive but realistic schedule for completion of tracker
- ❖ Critical path items are clearly identifiable and receiving special emphasis
- ❖ Greatest risk is major design flaw that would require fundamental changes: most likely somewhere in the hybrid or DAQ.

Important to have working prototypes ASAP.

- ❖ Software is also an important piece. A few projects are focal points for the tracking system. These will be discussed further in software sessions.

